Motion Control Valves

1CE90


Overcenter Valve, Standard, Direct Acting, Internal Drain, Port 3 Pilot

350 bar [5000 psi] • 90 l/min [24 US gpm]



This is a direct acting overcenter valve, which is a pilot assisted relief with a free flow check. With the relief valve set at approximately 1.3 times the maximum load induced pressure, the valve will prevent flow from port 1 to 2. When pilot pressure is applied to port 3, the valve will meter the flow from port 1 to 2, compensating for any change in pilot pressure due to over-running or unstable loads. Free flow takes place from port 2 to port 1 through the check portion of the valve. These valves are ideal in most applications bringing stability, load holding, and hose failure protection when the valve is mounted onto or into the actuator. The spring chamber is connected to the valve port 2, so any back pressure will increase the pilot pressure required to keep the valve open and the pressure at which the valve will open as a relief valve. This is also available in a dual housing for bi-directional control.

SCHEMATIC




■ PERFORMANCE DATA

Rated pressure	350 bar [5000 psi]
Rated flow	90 l/min [24 US gpm]
Max total relief pressure	350 bar [5000 psi]
Max recommended load pressure at max setting	270 bar [3900 psi]
Pilot Ratio	4:1, 8:1
Leakage	0.3 ml/min nominal [5 drops/min]
Weight	0.29 kg [0.63 lb]
Cavity	A12336

Danfoss

DIMENSIONS

mm [in]




Turn CW to increase pressure setting and CCW to decrease pressure setting.


Torque lock nut to 20-25 Nm [15-18 ft lbs]

Installation torque 60 Nm [44 ft. lbs]

PERFORMANCE CURVES

Pressure Drop





8:1 Pilot Ratio


Motion Control Valves

1CE90

Overcenter Valve, Standard, Direct Acting, Internal Drain, Port 3 Pilot 350 bar [5000 psi] • 90 l/min [24 US gpm]




1CEE95 (dual)



Danfoss

DIMENSIONS

mm [in]



MODEL CODE

